Notification dated 2nd February 1904.

ITTEGEGUD.

In accordance with Section 16 (1) of Regulation No. III of 1903 for the improvement of the City of Mysore, a scheme has been prepared for the area known as Ittegegud in Nazarbad Mohalla. The area is bounded on the north by Cooppanna's gardens, on the east by Mooneswara temple road and on the south and west by the Doddakere water spread. The area is divided into three drainage blocks bearing Nos. 39, 40 and 71. Particulars of the scheme, a map of the area comprised therein, and a statement specifying the land proposed to be acquired may be seen between 11 A.M. and 5 P.M. on office days at the Chairman's office now being held in the premises known as Lacey's Court.

2. The improvements consist of—

(1) The construction of drains and the diversion of sewage, at present polluting Doddakere to Captain Purchase's open drain in the ditch to the east of the Fort.
(2) The opening out of new roads, the widening of existing lanes and the entire removal of insanitary huts to relieve congestion.
(3) The provision of four public *latrines of 12 seats each.*

Details of new roads to be opened and the improvement of existing lanes.

Block No. 39.—In all six roads the most important of which is a road running from north to south parallel to Mooneswara temple road, and to the west of it.

Block No. 40.—Six roads of minor importance will be dealt with. A drivable road in prolongation of the westernmost road, in this block is proposed to be opened keeping it sufficiently high above the water spread of Doddakere to meet the Race-course road very near the tunnel across the Karanji tank drainage.

Block No. 71.—Will be dealt with by the bodily removal of insanitary dhobi huts and the opening of four minor roads.

Notification dated 2nd February 1904.

IDGA EXTENSION.

It is hereby notified in accordance with Section 16 (1) of Regulation No. III of 1903, that a scheme for the improvement of the Idga Extension has been prepared. The said extension is bounded on the north by the old City rampart, on the south by the Bakshi Budankhan's street, on the east by Anegondi Ars' street and on the west by Purnaiya's nallah and lands adjoining. The plans and other details of the scheme may be seen at the Chairman's Office held in Lacey's Court during office hours.

The improvements mainly consist of the drainage of the locality and the acquisition of lands for the housing of the poor, that would be displaced in the improvements of the town.

Notification dated 2nd February 1904.

JALAPURI AND KARNAPURA EXTENSION.

In pursuance of Section 16 (1) of Regulation No. III of 1903, it is hereby notified that a scheme for the improvement of the area known as the Jalapuri Extension of the Mysore City has been prepared: involving (1) the drainage of the area, (2) the acquisition of lands for building sites for the poor, and the acquisition of a few huts. The extension is on a spur to the north-east of the town, with a valley running round it, excepting on the south. A drivable road connecting Hale Nazarbad road with the travellers'bungalow road forms its boundary on the south. The plans of the extension and of the several improvements intended can be seen at the Chairman's Office now located in the building known as Lacey's Court during office hours.

MYSORE CITY IMPROVEMENT TRUST BOARD.

PROCEEDINGS OF A MEETING OF THE BOARD OF TRUSTEES HELD IN THE CHAIRMAN'S OFFICE ON THE 1ST FEBRUARY 1904.

PRESENT.

Mr. D. Sitaram Rao, Chairman.
Dr. P. S. Achyuta Rao, Civil Surgeon.
Mr. K. Srinivasa Rao, Vice-President.
„ Mahomed Jaffer Saheb, Police Superintendent.
„ Anantharajiah, Merchant and Municipal Commissioner.
„ M. Venkatakrishnaiya, Municipal Commissioner.
„ M. C. Ranga Iyengar, Municipal Commissioner.

ABSENT.

Mr. E. Maconochie, I.C.S.

I. Read Sub-Committee's proceedings dated 27th January 1904 about the selection of sites for the construction of experimental houses and drains at Idga and Jalapuri Extensions, and approved of the same.

II. In pursuance of the proceedings of Board's meeting on the 29th January at Chetnahalli Extension, in regard to the acquisition of land for the location of Palace servants, resolved that the site as particularized in the margin consisting of 111 acres, which includes the land indicated as required for Palace servants, by the Palace Sub-Committee, in their alternative proposal to the Government, in their proceedings dated 17th September 1903, be acquired. The acquired area be aligned, drained, roads formed, and otherwise completed for building purposes, eastewar. After the requirements of the Palace are met, the rest be reserved for superior classes of houses.

*Bounded on the north by the lane to the south of Vani Vilas road and to the north of Dodda Holgeri, on the west by the Viceroy road and the Bennehardenahalli feeder, on the south also by the Bennehardenahalli feeder, and on the east by the Bennehardenahalli feeder, the lane to the north of Sinceerkatte and the road from the new Sunnadakere market to the Mysore Manantoddy road.

Resolved further that the people of Dodda Holagere who would be displaced be located to the south of Veeranah's Weavers' lines.

(*Enclosure A.*)

Proceedings of the Sub-Committee appointed under Resolution No. II of the Board, dated 27th January 1904.

Present.

Mr. D. Sitarama Rao, Chairman.
Dr. P. S. Achyuta Rao, Civil Surgeon.
Mr. K. Srinivasa Rao, Vice-President.
" Anantharajaiya, Municipal Commissioner.
" M. Venkatakrishnaiya and the Municipal Commissioner of Mandi Mohalla, Mr. Madappa, were also present.

The members met at the Mochighat Police Station and proceeded to inspect the sites intended for building at the Idga Extension. The Sub-Committee selected the sites shown in the accompanying plan for building experimental houses of the types noted on the plan. It is also intended to build drains on an experimental measure in the conservancy lanes indicated on the plan.

The members then proceeded to Jalapuri Extension and inspected all the available sites for building purposes. It was resolved to build about 46 houses costing Rs. 125 each and about 12 of the 250 Rs. type on sites indicated on the accompanying plan. They further determined to build experimental drains in the conservancy lanes indicated on the plan.

(*Enclosure B.*)

Proceedings of a Meeting of the Board of Trustees in pursuance of Resolution No. V, dated 27th January 1904.

The members of the Board excepting Mr. E. Maconochie, I.C.S., met near the Chetnahalli Extension at about 8 A. M. on Friday the 29th January 1904, and went over the ground proposed for the location of the Palace servants by the Palace Sub-Committee in their report to Government, No. 38 dated 5th October 1903, and it was resolved to meet at the Chairman's office on Monday 1st February 1904 at about 5 P. M. to arrive at final proposals in the matter.

Dated 21st February 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, up to 15th March 1904, for the construction of drains and works relating to them. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for the drainage of No. I drainage area of Mysore City," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of work to be done in No. 1 Drainage area of Mysore City.

No.	Items of work.	Per	Approximate quantity.
1	Earthwork excavation for constructing open drains, etc. ...	C. yds.	5,298
2	Machine-ground surki mortar concrete for constructing drains ...	C. ft.	79,974
3	Machine-ground surki mortar plastering for drains ...	Sqr.	1,411·47
4	Cement plastering for drains	Sqr.	1,411·47
5	Machine-ground surki mortar concrete for filling foundation, for silt traps etc.	C. ft.	3,683
6	Burnt brick in machine-ground surki mortar for silt traps ...	do	28,627
7	Machine-ground surki mortar plastering for silt traps ...	Sqr.	322·92
8	Burnt stone slabs 3" to 4½" thick for covering drains ...	S. ft.	10,723
9	Do 2½" to 3" thick	do	338
10	Laying of stoneware glazed pipe 4" dia., including excavation and refilling for an average depth of 4' (when pipes are supplied.)	R. ft.	2,840
11	Laying of stoneware glazed pipe 9" dia. do do do ...	do	250
12	Coping with burnt brick in mortar and plastering ..	do	1,376
13	Arch work in burnt brick in machine-ground surki mortar ...	C. ft.	·53
14	Teakwood door (3'×6') including frame to the washing platform at latrines.	Each	16

N. B.—Materials for construction of drains, *viz.*, broken metal of size specified, burnt lime and burnt brick powder (surki), may be tendered for separately for delivery in any part of the area comprised.

Machinery for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Dated 21st February 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvement Division, up to 15th March 1904, for the construction of drains and works relating to them. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, Mysore, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for constructing drains and works connected therewith in Nazarbad," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejeted tenders will be returned.

Statement showing the quantity of drainage works to be done in Nazarbad.

No.	Items of work.	Per	Approximate quantity.
1	Earth work excavation for constructing open drains, etc. ...	C. yds.	3,584
2	Machine-ground surki mortar concrete for constructing drains. ...	C. ft.	48,279
3	Machine-ground surki mortar plastering for drains	Sqr.	838·71
4	Cement plastering for drains	Sq.	838·71
5	Machine-ground surki mortar concrete for filling foundation of silt-traps, storm-overflows and manholes, etc.	C. ft.	6,495
6	Burnt brick in machine-ground surki mortar do ...	C. ft.	22,226

	Items of work.	Per	Approximate Quantity.
7	Machine-ground surki plastering for silt-traps, storm-overflows and manholes, etc.	Sqr.	274·36
8	Coping with burnt briel in mortar and plastering .. .	R. ft.	1,032
9	Burnt stone slabs 3" to 4½" thick for covering drains	S. ft.	3,440
10	Do do 6" do	S. ft.	80
11	Laying of stoneware glazed pipes (4" diameter) including excavation and refilling for an average depth of 4 feet. (Note—Pipes will be supplied.)	R. ft.	800
12	Do do (6" diameter) do ..	R. ft.	6,035
13	Teakwood door with frame (3'×6') to the washing platform at latrines	Each	12

N. B.—Materials for construction of drains, *viz.*, broken metal of size specified, burnt lime and surki brick powder, may be tendered for separately for delivery in any part of the area comprised.

It is to be noted that machinery for grinding mortar will be made availble, the tenderer bearing the charges for the preparation of the mortar.

Dated 20th February 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, up to 15th March 1904, for the construction of drains and works appertaining thereto. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains and works appertaining thereto in Ittigegud;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Ittigegud.

No.	Items of work.	Per	Approximate quantity.
1	Earthwork excavation for constructing open drains etc. ...	C. yds.	6,122
2	Machine-ground surki mortar concrete for constructing drains ...	C. ft.	16,951
3	Do do plastering for drains ...	Sqr.	324·15
4	Cement plastering for drains	do	324·15
5	Machine-ground surki mortar concrete for filling foundation of silt traps, storm overflows, etc.	C. ft.	5,355
6	Burnt brick in machine-ground surki mortar do ...	do	14,851
7	Machine-ground surki mortar plastering for silt traps, storm overflows, etc.	Sqr.	1[illegible]73

	Items of work.	Per	Approximate quantity.
8	Burnt stone slabs 3" to 4½" thick for covering drains	S. ft.	1,776
9	Do 6" do do	do	21
10	Laying of stoneware glazed pipes 6" diameter, including excavation and refilling an average depth of 4' (when pipes are supplied).	R. ft.	10,498
11	Laying of stoneware glazed pipes 8" do do ...	do	800
12	Coping with burnt brick in mortar and plastering ...	do	688
13	Teakwood doors (3'×6') including frame to the washing platform at latrines.	Each	8

N. B.—Materials for construction of drains, *viz.*, broken metal of size required, burnt lime, and surki brick powder, may be tendered for separately for delivery in any part of the area comprised.

Machinery necessary for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Notice, dated 21st February 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Improvement of the City of Mysore, up to 15th March 1904, for the building of drains and other subsidiary works. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains and subsidiary works in Idga Extension of the Mysore City," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement o the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Idga Extension.

	Items of work.	Per	Approximate quantity.
1.	Earthwork excavation for constructing open drains, etc.	...C. yds.	1,761
2.	Machine-ground surki mortar concrete for constructing drains, etc. ..	C. ft.	15,541
3.	Machine-ground surki mortar plastering for drains	Sqr.	265·00
4.	Cement plastering for drains	Sqr.	265·00
5.	Machine-ground surki mortar concrete for filling foundation of cisterns, etc.	C. ft.	204
6.	Burnt brick in machine-ground surki mortar for cisterns, etc. ..	C. ft.	612
7.	Machine-ground surki mortar plastering for brick work	Sqr.	10·20
8.	Burnt stone slabs 3" to 4½" for constructing drains with 1¼ feet depth of excavation.	S. ft.	4,340
9.	Burnt stone slabs 3" to 4½" for covering drains	S. ft.	2,783

N. B.—Materials for construction of drains, *viz.*, broken metal of specified size, burnt lime and burnt brick powder (surki), may be tendered for separately for delivery in any part of the area comprised.

Machinery for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

455

Dated 21st February 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Improvement of the Mysore City, up to 15th March 1904 for the construction of drains and works relating to them. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains in Jalapuri Extension," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Jalapuri Extension.

	Items of work.	*Per*	*Approximate quantity.*
1	Earthwork excavation for constructing open drains, etc. . .	C. yds.	2,640
2	Machine-ground surki mortar concrete for constructing drains ...	C. ft.	29,055
3	Machine-ground surki mortar plastering for drains ...	Sqr.	482·76
4	Cement plastering for drains	,,	482·76
5	Machine-ground surki mortar concrete for filling foundation of cisterns, etc.	C. ft.	336
6	Burnt brick in machine-ground surki mortar for cisterns, etc. ..	,,	1,008
7	Machine-ground surki mortar plastering for brick work ...	Sqr.	14·00
8	Burnt stone slabs 3" to 4½" for constructing drains with 1½ feet depth of excavation.	S. ft.	7,750
9	Burnt stone slabs 3" to 4½" for covering drains	,,	3,686
10	Burnt stone slabs 2½" to 3" for putting to the sides of drains ..	,,	2,218

N. B.—Materials for construction of drains, *viz.*, broken metal of specified size, burnt lime and burnt brick powder (surki) may be tendered for separately for delivery in any part of the area comprised.

Machinery for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of mortar.

D. SITARAM RAO,
Chairman of the Board of Trustees, Mysore.

MYSORE GOVERNMENT STATIONERY DEPOT.

TENDERS FOR THE SUPPLY OF INDIAN-MADE PAPERS.

Notice dated 4th February 1904.

Sealed tenders for the supply of Indian-made papers required for the Government of Mysore during the official year 1904-05, will be received by the Superintendent of Stationery, Mysore Government, at his office at Bangalore, up to 26th March 1904.

2. Tenders should be superscribed "Tender for Indian-made papers for 1904-05" and should be accompanied by samples and by a deposit of Rs. 500 as earnest money, which will be returned after the disposal of tenders to all unsuccessful tenderers and be liable to be forfeited if the successful tenderers fail to fulfill the conditions of their contract. In cases where tenderers may deposit Government Promissory Notes, they should endorse the same payable to the "Superintendent of Stationery Depot, Mysore Government, Bangalore."